Sl No.	Approved Qty.	Description	Unit	Approved Tender Rates of BYADIGERE HONNESH SHIVAKUMAR	
				In Figures	In Words
14	2246.97	Providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	39	Rupees Thirty Nine Only
15	112.35	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50 / 75mm compacted thickness with 3.3% bitumen but excluding cost of primer / tack cost with lead upto 1km including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5, With 80/100 grade bitumen, etc complete as per specifications and directions of engineer in charge of the work	Cum	5500	Rupees Five Thousand Five Hundred Only
16	3189.47	Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding clearing of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	22	Rupees Twenty Two Only
17	127.58	Providing and laying bituminous concrete 40mm thick with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification NO. 509, With bitumen 80/100, etc complete as per specifications and directions of engineer in charge of the work	Cum	9100	Rupees Nine Thousand One Hundred Only
18	114.86	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. etc complete as per specifications and directions of engineer in charge of the work	Cum	63	Rupees Sixty Three Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Sl No.	Approved Qty.	Description	Unit	Approved Tender Rates of BYADIGERE HONNESH SHIVAKUMAR	
				In Figures	In Words
8	39.2	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	64	Rupees Sixty Four Only
9	458.08	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	188	Rupees One Hundred Eighty Eight Only
10	62.16	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, etc complete as per specifications and directions of engineer in charge of the work	Cum	4290	Rupees Four Thousand Two Hundred Ninety Only
11	40.47	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qtl	5500	Rupees Five Thousand Five Hundred Only
12	478.37	Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) etc complete as per specifications and directions of engineer in charge of the work	Cum	102	Rupees One Hundred Two Only
13	674.09	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1000	Rupees One Thousand Only

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ,
ಬ.ಬೆ.ಮ.ಪಾ. ರಾಜರಾಜೇಶ್ವರಿ ವಲಯ
ಸಹಕಾರನಗರ, ಬೆಂಗಳೂರು-92.

BRUHAT BANGALORE MAHANAGARA PALIKE

Item No. 3673

APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/04/2012-13 Dated : 10/07/2012

Name of the Work : Improvements of Nanjappa Circle in Ward No. 09, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of BYADIGERE HONNESH SHIVAKUMAR	
				In Figures	In Words
1	108	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50 m and removing the debris to a distance upto 200m, etc complete as per specifications and directions of engineer in charge of the work	Cum	110	Rupees One Hundred Ten Only
2	162	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200 m (within average thickness of 15 cms), etc complete as per specifications and directions of engineer in charge of the work	sqm	33	Rupees Thirty Three Only
3	436.07	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	cum	74	Rupees Seventy Four Only
4	30.73	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, etc complete as per specifications and directions of engineer in charge of the work	Cum	3230	Rupees Three Thousand Two Hundred Thirty Only
5	11.76	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	2350	Rupees Two Thousand Three Hundred Fifty Only
6	23.52	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	2760	Rupees Two Thousand Seven Hundred Sixty Only
7	2.35	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, etc complete as per specifications and directions of engineer in charge of the work	Cum	3575	Rupees Three Thousand Five Hundred Seventy Five Only

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ.
ಬ.ಬೆ.ಮ.ಪಾ. ರಾಜಕಾಲುವೆ ವಲಯ
ಸಹಕಾರನಗರ, ಬೆಂಗಳೂರು-92.

This document was created with Win2PDF available at http://www.win2pdf.com.
The unregistered version of Win2PDF is for evaluation or non-commercial use only.
This page will not be added after purchasing Win2PDF.